

# Optimalisasi kinerja proyek dengan penggunaan metode beton pracetak terhadap biaya dan waktu : studi kasus kebagusan city

Try Puji Satoso, author

Deskripsi Lengkap: <https://lib.ui.ac.id/detail?id=20283412&lokasi=lokal>

---

## Abstrak

Kebutuhan akan hunian pada kota-kota besar di Indonesia semakin meningkat seiring dengan semakin sedikitnya lahan yang dapat digunakan sebagai lahan hunian. Sehingga lahirnya fenomena investasi hunian yang sangat meningkat pesat dalam bentuk high rise building. Dengan potensi investasi yang besar ini maka para investor akan menuntut kinerja proyek yang lebih tinggi dengan pelaksanaan proyek dengan waktu yang cepat dan biaya yang efektif. Untuk memenuhi tuntutan tersebut serta mendukung perkembangan teknologi dalam industri konstruksi, maka dibutuhkan metode konstruksi yang optimal yaitu metode konstruksi dengan menggunakan beton pracetak (precast concrete) untuk pekerjaan struktur dan pekerjaan arsitektur pada bangunan gedung tinggi. Namun kenyataannya, penggunaan metode beton pracetak ini masih dilakukan secara acak baik itu pada pekerjaan struktur maupun pekerjaan arsitektur. Sehingga belum dapat dipastikan apakah pelaksanaan metode pracetak dapat mengoptimalkan kinerja proyek.

Adapun tujuan dari penelitian ini adalah untuk menghasilkan model metode pelaksanaan beton pracetak yang paling optimal terhadap kinerja proyek. Penelitian ini membandingkan pelaksanaan metode beton pracetak dengan metode konvensional pada pekerjaan struktur dan pekerjaan arsitektur untuk mendapatkan perencanaan penjadwalan proyek dan biaya pelaksanaan yang paling efektif dari kinerja proyek. Hasil penelitian menunjukkan dari keempat kombinasi metode yang dilakukan, kombinasi metode 2 yaitu pekerjaan pekerjaan balok dan pelat dengan metode beton pracetak dan pekerjaan dinding facade dengan metode konvensional merupakan kombinasi yang paling efektif dengan waktu dan biaya proyek yang paling optimal.

.....The need for housing in big cities in Indonesia increased along with the decreasing amount of land that can be used as residential land led to the phenomenon of residential investment that increased rapidly in the form of high-rise building. In addition to high investment potential, investors will require higher projects performance with prompt implementation time and cost effective. In order to fulfil this requirement and to support technology development in construction industry, the optimal construction is highly needed by using precast concrete for structural and architectural works on high rise building project. However, the use of this precast concrete method is still implemented randomly, whether on structural or architectural work.

Therefore, the implementation methods that can optimize the performance of precast projects has not been established.

This research aims to produce the optimal model of precast concrete implementation method on the structural and facade work with the most optimum project performance. This research compared the implementation of the precast concrete method and conventional methods on structural and architectural to obtain the most effective project schedule planning and implementation cost. The research result shows that among four combination methods, the second method that used the combination of precast on beam and plat works and conventional method on wall and facade works is the most effective combination with optimal time and project cost.